

## 3.2 Blends of recycled materials as sustainable alternatives for backfilling sewer trenches

E. Yaghoubi<sup>1</sup>, A. Al-Taie<sup>2</sup>, S. Fragomeni<sup>3</sup>, E. Gmehling<sup>4</sup> and S. Trikha<sup>5</sup>

<sup>1</sup>Victoria University, D304, 100 Ballarat Rd, Footscray, VIC 3011, PH (+61) 3 9919 4804; email: [Ehsan.yaghoubi@vu.edu.au](mailto:Ehsan.yaghoubi@vu.edu.au)

<sup>2</sup>The University of Melbourne, B210, Block B, Parkville, VIC 3010, PH (+61) 3 9035 8557; email: [aaltaie@unimelb.edu.au](mailto:aaltaie@unimelb.edu.au)

<sup>3</sup>Victoria University, D302, 100 Ballarat Rd, Footscray, VIC 3011, PH (+61) 3 9919 5212, email: [Sam.Fragomeni@vu.edu.au](mailto:Sam.Fragomeni@vu.edu.au)

<sup>4</sup>Ground Science, 13 Brock St, Thomastown VIC 3074, PH (+61) 3 9464 4617, email: [ernie@groundscience.com.au](mailto:ernie@groundscience.com.au),

<sup>5</sup>City West Water, 1 McNab Ave, Footscray VIC 3011, PH (+61) 3 9313 8966, email: [shalini.trikha@citywestwater.com.au](mailto:shalini.trikha@citywestwater.com.au)

### ABSTRACT

In this project, the suitability of four blends of recycled materials comprising different proportions of recycled glass, plastic, and tyre aggregates as alternative backfilling materials for deep excavated trenches was investigated. This paper presents results of an extensive testing program carried out for selecting two most appropriate blends for backfilling of trenches located in non-trafficable areas. These blends will be used for construction and instrumentation of trial sites for deformation monitoring over 12 months. Physical properties such as particle size distribution, maximum and minimum density, compaction properties, and field capacity of the blends were determined. Further, an application-specific geotechnical testing methodology was developed. This included determination of the dry density achieved using a proposed sand-raining technique (SRT) to simulate the real-life trench backfilling procedure and determination of the compressibility of the blends using a modified oedometer test. The SRT results showed that the obtained dry density (DD) increased as moisture content (MC) and height of drop increased. Based on the relative density achieved through the SRT compaction and the compressibility properties, Blends 2 and 4 showed the most advantageous characteristics. This paper presents the developed testing procedures and discussions on the results leading to the selection of the two most suitable blends for the proposed application. The paper also makes discussions on the stress-strain conditions expected on site and potential downfalls of the proposed application. The outcomes of this research aim to promote sustainable geotechnical design and construction by improving the industry's confidence in utilising recycled materials.

*Keywords:* recycled aggregates, trench backfill, sand-rain technique, compressibility, field compaction.

### 1 INTRODUCTION

The worldwide movement toward sustainability encourages continuous and persistent studies on new strategies of recycling and reusing waste material in a range of applications (Lindsey 2011). Since civil engineering construction projects have a significant demand for construction materials, they are a common destination for the reuse of recycled aggregates. Various studies have shown the suitability of using recycled materials, in particular recycled plastic, glass and tyre in civil engineering applications (Fauzi et al. 2016; Imteaz et al. 2012; Imteaz et al. 2018; Kamaruddin et al. 2017). Sewer infrastructures backfilled with expansive clay or large soil clods result in poor backfill compaction during the variable seasonal cycles. Heavy winter rains expose these conditions and result in unexpected ground movements and subsequent failures, especially in rigid sewer pipes made of concrete. This issue is aggravated in narrow trenches for small diameter sewer pipes that are deeper than 1.5m where the quality control of the backfilled trenches can be challenging, if feasible, due to safety limitations restricting the field staff entering the trench for geotechnical testing. Temporary shoring or benched excavation of sidewalls are measures that can accommodate safe presence of testing staff in the trench for quality control. However, site conditions or space limitations may not always allow for such measures. Lack of proper quality control can lead to further settlements at the surface and affects both building structures and boundary fence lines. A potential solution is the application of blends of recycled

materials that have self-compacting characteristics, have small volume changes with moisture changes or require less compactive effort to reach the desired relative density and thus exhibit less settlement on the surface.

The current study aims to investigate the utilisation of recycled material blends as sewer trench backfill material in order to minimise the settlement of sewer backfill, in particular at non-trafficable manholes or sewage pit locations, which result in these structures protruding the surface, causing trip hazards as the backfill soils settle. The current project comprises application-specific laboratory testing programs, as well as the construction of a full-scale site trial for performance monitoring. This paper presents the geotechnical results and discussions to determine two mix designs of recycled material blends for the construction of the trial sites. The trial site is located in a greenfield area in the border of Tarneit and Truganina, Victoria. The Geological Survey of Victoria 1:63,360 Melbourne map sheet indicates that the site is underlain by Quaternary Age Newer Volcanics, comprising residual clay overlaying variably weathered basalt rock.

To the best of the authors' knowledge, this is the first time an investigation of 100% recycled material blends for sewer trench backfilling is being undertaken, leading to the construction of a real-life full-scale site trial. The outcome of this research can lead to an increased market demand for recycled materials, in particular, recycled plastic, recycled glass and tyre derived aggregates and reduce the reluctance of end-users for investment in the new innovative solutions.

## 2 METHODOLOGY

### 2.1 Materials and proportions

Hand mixed blends of 100% recycled materials including recycled glass (RG), recycled plastic (RP) and tyre derived aggregates (TDA) were used. The materials were supplied from local recycling facilities in Victoria, Australia. The specific gravities of the recycled materials were obtained following the AS1289.3.5.1 (2006) procedure to be 2.48, 1.1 and 1.12 for RG, RP and TDA, respectively.

The strategy to determine a suitable blend was selecting blends having a spectrum of different percentages of recycled materials with gradation curves that fall within Class 4 upper and lower band gradation (VicRoads 2013) as recommended by MRWA (2013). Consequently, four blends with different recycled material contents were selected as presented in Table 1.

Figure 1 shows one of the proposed blends in a Perspex cell with a perforated base plate used for the determination of the field capacity. Field

capacity is the amount of moisture held in soil after excess water has drained.



Figure 1. Blend 1 in a Perspex cell

Table 1: RG, RP and TDA ratios in blends 1 to 4

Recycled materials	% by Mass			
	Blend 1	Blend 2	Blend 3	Blend 4
RG	77	77	69	84
RP	6	9	6	5
TDA	17	14	25	11

### 2.2 Standard Compaction

Standard Proctor compaction test was performed according to AS1289.5.1.1 (2017). This test was carried out to obtain the optimum moisture content (OMC) and maximum dry density (MDD) based on the traditional compaction method as a benchmark.

### 2.3 Sand-Rain Technique

The sand-rain technique (SRT) setup developed in this study is demonstrated in Figure 2. The system consists of five parts: beam with adjustable height, hanging rod, hopper, collection tank and sample collector. The cross-section of the hopper from the top is 200(L)×200(W) mm and the short height is 200mm while the long height is 450mm. The hopper is equipped with a lid which opens up to 50mm. The beam and hanging rod allow the hopper to move in horizontal and vertical directions, respectively. The mould with 150mm diameter and 180mm height is placed in a tank of 370(L)×470(W)×700(H) mm. The base of the mould has 2mm diameter holes (approximately 1200 holes/m<sup>2</sup>) to allow drainage. The position of the hopper was adjusted by moving the beam vertically to allow for various heights of drop (HD) of the materials. The HD varied from 500mm to 2000mm. The mould was placed in the collection tank to collect the materials dropped out of the mould. The mould was raised on a collar to allow water draining from the base.

The moisture content (MC) of the blend varied from 3% (as received MC) to 18%. The MC of 18% was selected as preparing wetter samples did not lead to considerably greater dry density. At high MCs (≥15%), after dropping the materials the blend was left in the mould for 10 minutes allowing the water to

drain from the base of the mould. The moisture at this state was “field capacity” at which no extra water was drained off the sample due to gravity. Finally, the post-test MC was obtained and the dry density was determined. This procedure was repeated at various MCs and HDs.




Figure 2. Sand-rain technique setup

### 2.4 Modified oedometer test

The compressibility of the blends was investigated following the AS1289.6.6.1 (1998) procedure with

modifications on the mould size and compaction of the sample. The inside walls of a mould with 150mm diameter and 120mm height were lubricated using silicon grease to reduce the errors due to friction. The base of the mould had 2mm through holes to allow drainage. A filter paper was used on the base and the sample was then placed into the mould in three layers to a total height of 75mm to provide a diameter to height ratio of 2, as recommended by AS1289.6.6.1. The oedometer test set up is presented in Figure 3.



Figure 3. Modified oedometer test setup

Several loading stages of 6, 12.5, 25, 50, 100, 200kPa were applied to the sample. At each loading step, the settlement was recorded and once no further settlement was achieved, the next load was applied. At the end of the test, the weight of the sample and the MC were measured to calculate the final density/void ratio. Also, the test data was collected to plot the axial strain-stress relationship. A similar procedure was undertaken for testing the compacted samples under saturated conditions. For the saturated samples, the mould was inundated in a water bath after a low surcharge of 1kPa was imposed on the sample.

### 3 RESULTS AND DISCUSSIONS

#### 3.1 Particle size distribution

The PSD of the blends is presented in Figure 4 together with the upper and lower limits of Class 4 gradation based on VicRoads 2013. PSD curves show that the blends fall within the Class 4 gradation on the coarse side (>2.36 mm); however, they are slightly outside the lower limit on the fine side (<2.36 mm).

#### 3.2 Standard Compaction

The standard Proctor OMC and MDD for Blends 1 to 4 were (8.5%, 1.34 t/m<sup>3</sup>), (9.5%, 1.36 t/m<sup>3</sup>), (11%, 1.25 t/m<sup>3</sup>) and (9%, 1.37 t/m<sup>3</sup>), respectively. Evidently, the OMC and MDD for Blends 1, 2, and 4 were close (9% and 1.36 t/m<sup>3</sup> as an average). However, the MDD for Blend 3 was noticeably lower than those of other blends.




Figure 4. PSD of the four blends

#### 3.3 Sand-rain technique

The relationship of dry density (DD) to post-test moisture content (MC) at different height of drops (500, 750, 1000, 1500 and 2000 mm) is plotted for Blends 1 to 4 in Figures 5 to 8, respectively. In these plots, the compaction curves achieved through standard compaction are also presented for comparison. Data labels show the initial (pre-compaction) MCs.




Figure 5. DD vs MC at various HD for Blend 1

Figures 5 to 8 show that the DD increased as MC increased at a constant HD. For initial MCs equal to or greater than 15% after dropping, the water drained from the sample and resulted in a post-test MC between 9% and 12.7%. Interestingly, this range aligns with the measured field capacity of the blends as presented in Table 2. As an example, in one of the trials, Blend 4 was prepared at MC of 18% and dropped from HD of 2000 mm. The blend was left for 10 minutes for draining until no further drainage occurred. The post-test MC was measured to be 9.7%. The MC of Blend 4 at its field capacity was measured to be 9%. For samples prepared at MC≥15%, the combined effect of higher lubrication and greater densification (lower voids) led to a greater drainage. This resulted in turning the compaction curve into the opposite direction and thus, two DDs for the same MC. The lower DD was corresponding to the lower initial MC with no drainage and the higher DD was corresponding to the higher initial MC which reduced through drainage to reach the post-test MC.




Figure 6. DD vs MC at various HD for Blend 2




Figure 8. DD vs MC at various HD for Blend 4




Figure 7. DD vs MC at various HD for Blend 3

Figures 5 to 8 also show that as HD increased, DD increased at a constant MC and consequently, it was expected that the post-compaction MC decreased as the height of drop increased. The increase in HD from 1500mm to 2000mm led to an increase in DD for blends with low MC. Once MC became close to 15% or higher, the change in DD became negligible. For Blend 4, the change in HD did not change the DD even for low MC ranges.

From the results, it may be concluded that the OMC and MDD of SRT compaction were achieved by dropping the blends from HD equivalent to 2000mm at high MCs ( $\geq 15\%$ ). The OMC and MDD for Blends 1 to 4 were determined to be (18%, 1.3 t/m<sup>3</sup>), (15%, 1.35 t/m<sup>3</sup>), (15%, 1.13 t/m<sup>3</sup>) and (18%, 1.4 t/m<sup>3</sup>), respectively. Post-test MCs were 9.2, 9.7, 10.3 and 9.7 for Blends 1 to 4, respectively.

The dry densities obtained through the sand-rain technique for Blends 1, 2 and 4 (Table 2) show that a density comparable to MDD of standard Proctor can be achieved at a HD of 2000mm. The relative density with respect to max/min density test results (AS1289.5.5.1 2016) was greater than 80% for Blends 1, 2 and 4, being 82.5%, 85.5% and 83.5, respectively and the percentage of MDD obtained from the standard Proctor compaction were 97%, 99% and 102.2%, respectively (Table 2).

The relative density of Blend 3 was 52% which was significantly lower than the other blends. Therefore, Blend 3 was deemed unsuitable for construction of the full-scale site. The lower relative density of the backfilled material can lead to greater potential settlements after construction.

Table 2: Results of different compaction tests and field capacity test

Blend		1	2	3	4
Max/Min Density	Maximum density AS1289.5.5.1	1.38	1.41	1.27	1.50
	Minimum density AS1289.5.5.1	1.02	1.08	1.01	1.05
Standard Proctor (SP)	Estimated MDD (t/m <sup>3</sup> )	1.34	1.36	1.25	1.37
	Estimated OMC (%)	8.50	9.50	11.00	9.00
	Relative density	91.5	88	93.7	77.8
Sand-Raining technique (SRT)	Estimated MDD (t/m <sup>3</sup> )	1.30	1.35	1.13	1.40
	Height of drop (mm)	2,000	2,000	2,000	2,000
	Target MC (%)	18.0	15.0	15.0	18.0
	Post-test MC (%)	9.2	9.7	10.2	9.7
	Relative density (%)	82.5	85.5	52	83.3
	Percentage of Field capacity (%)	97	99.3	90.4	102.2

### 3.4 Compressibility of the blends

A modified 1-D oedometer testing procedure as described in Section 2.4 was carried out to select two blends from Blends 1, 2 and 4 for construction of the trial site. The samples were prepared at the OMC and MDD achieved through the SRT compaction. Figure 9 shows that the total axial strain achieved in Blends 1, 2 and 4 were lower than that of Blend 1 under the loading steps mentioned in Section 2.5. Consequently, based on the oedometer test results,

Blends 2 and 4 were selected for the construction of the full-scale trial site.

### 3.5 Discussion on the construction MCs and potential segregation

Mixing the blends with MCs greater than 15% (about 6% greater than the field capacity of the blends) may result in excess water ingress into the natural ground and cause settlements or subsidence. On the other hand, densities achieved through SRT test show that

the blends may not achieve a satisfactory density if mixed with a MC close to their field capacity (Figures 5 to 8). Dropping Blends 2 and 4 at post-test MCs (9.7%), results in dry densities of 1.2 t/m<sup>3</sup> and 1.33 t/m<sup>3</sup>, respectively (Figures 6 and 8).




Figure 9. Axial strain-stress relationships for Blends 1, 2 and 4 at OMC and MDD

It should be noted that the density achieved through SRT compaction is the loosest state of the densified blends. During the backfilling process, the surcharge of the upper layers causes further densification of the bottom layers. In addition, the backfilled area will be further compacted using the conventional field compaction techniques such as excavator's compaction plate. In the case of excavated trenches of this project, the top 0.5m will be backfilled with conventional materials (site-won soils or class 4 aggregates). Figure 10 shows a schematic profile of the trench with three zones, being the embedment zone, recycled material backfill zone, and conventional backfill zone. Considering the discussions above, it is expected that the final density of the blends falls between the DD achieved at MC of 9.7% and those achieved at MC>15% (Figures 6 and 8). Therefore, further compressibility assessment was carried out on samples prepared at MC of 9.7% and a density lower than the MDD achieved through SRT compaction.

Compressibility of Blend 2 was further assessed by preparing samples at (9.7%, 1.2 t/m<sup>3</sup>), (9.7%, 1.25 t/m<sup>3</sup>), (9.7%, 1.3 t/m<sup>3</sup>) to be compared with those of a sample at (9.7% and 1.35 t/m<sup>3</sup>). Also, Blend 4 was prepared at MC of 9.7%, and DD of 1.33 t/m<sup>3</sup> to be compared with a sample prepared at MC of 9.7% and MDD of SRT compaction (1.4 t/m<sup>3</sup>). For Blend 2, the change in axial strains obtained due to imposing a pressure up to 50kPa is minor for blends prepared at DD of 1.25 t/m<sup>3</sup>, 1.3 t/m<sup>3</sup> and 1.35 t/m<sup>3</sup>. Assuming a maximum density of 1.41 t/m<sup>3</sup> (AS1289.5.5.1) and a depth of 4m, the maximum surcharge at the bottom of the backfilled area is estimated to be 55kPa. The axial strain obtained by loading Blend 2 samples prepared at DD of 1.2 t/m<sup>3</sup> was considerably higher than that of the other blends (Figure 11). As discussed before, the surcharge from the ordinary backfilled zone, together with additional compactive effort using the excavator is expected to increase the DD from 1.2 t/m<sup>3</sup> to at least 1.25 t/m<sup>3</sup>. The axial strain shows a minor difference for Blend 2

samples prepared at the field capacity moisture content, and DDs of 1.25 to 1.35 t/m<sup>3</sup>.




Figure 10. Schematic profile of a backfilled trench

Figure 11 shows that the change in axial strain between the two Blend 4 samples under a pressure less than 100kPa was minor. The difference in axial strain between the loosest and densest state of the compacted Blend 4 was significant when the blends were subjected to a pressure greater than 100 kPa. As the bottom of the recycled material backfilled zone is at a depth of about 4m and assuming the maximum density (AS1289.5.5.1 2016) of Blend 4 (1.50 t/m<sup>3</sup>) the maximum surcharge can be calculated to be 59kPa which is significantly lower than 100kPa. Consequently, despite achieving a lower density compared to the MDD of SRT compaction, it is expected that a negligible difference in axial strain is caused due to mixing at lower moisture content. It should be noted that due to the granular nature of the blends, a large proportion of the deformation occurs during construction and unlike clay, consolidation settlement is not expected.




Figure 11. Axial strain-stress relationship for Blends 2 and 4 at post-test MC and DD ≤ MDD

It is anticipated that civil contractors will favour a load and dump technique similar to that used in normal backfill construction. Field trials will consider the influence of the drop height from the bucket, with elevated heights possibly required as the trench is filled to near the finished fill depth. Alternatives including an Aggie truck or volumetric mixer truck may be considered to control the height of drop. A potential concern during the backfilling procedure is the segregation of aggregates. According to the

studies of Tripathy et al. (2002) and Islam (2015), the OMC achieved in the standard compaction method is expected to result in a degree of saturation of 85%. The MC of 9.7% is close to OMC obtained by the standard Proctor compaction (9.5% for Blend 2 and 9% for Blend 4). At such a high degree of saturation, the surface tension on particles caused by moisture is expected to reduce the segregation of particles. This aligns with the laboratory observations of the sand-rain technique compactions undertaken at a height of drop of 2m.

Installation of optic fibre (O/F) cables will be carried out after backfilling. Figure 10 shows the indicative location of O/F cables each having several sensing points with 500mm spacing. The cables will be installed using a CPT rig by attaching the cable to the CPT rod and pushing the rod to the required depth. All cables will be connected to a data acquisition unit located on the surface using which settlement data can be collected in each site visit.

#### 4 CONCLUSION

Blends of recycled materials including recycled glass, recycled plastic and tyre derived aggregates were tested to investigate the feasibility of replacing these aggregates with the conventional backfill material in deep sewer trenches. Several laboratory tests including the sand rain technique were carried out to investigate the physical and mechanical properties of the four blends. Results showed that the dry density increased as moisture content and height of drop increased. Also, the dry density decreased as the tyre content increased. The MDD was achieved when a blend was prepared at a moisture content  $\geq 15\%$  and after dropping the blends from a height of 2m. At high moisture contents, the MDD obtained through the sand-rain technique approached the corresponding values obtained from the Proctor compaction and achieved  $> 80\%$  relative density.

Achieving greater relative density and exhibiting less compressibility response, Blends 2 and 4 were recommended for the construction of the trial sites.

To avoid the ingress of excess water into the natural ground due to moisture contents higher than the field capacity, backfilling of the sites with Blends 2 and 4 mixed at the MCs corresponding to their field capacity and height of drop of at least 2m is recommended for the construction of the trial sites.

Two possible downfalls with the proposed application recycled blends include potential creep settlement and environmental concerns, such as leachate seeping into the groundwater. These potential issues may limit the application of the proposed blends to trenches with low surcharges on the backfilled zone (such as non-trafficable areas) and areas away from groundwater table. The creep behaviour and leaching properties of the blends will be investigated as part of the future laboratory experiments of this project.

At the time of preparing this paper, the construction arrangements are being made for the next stage of the project.

#### 5 ACKNOWLEDGEMENTS

This project is supported through a Sustainability

Victoria grant from the Victorian Government's Recycling Industry Strategic Plan Fund. The recycled glass and tyre used in this project was donated by "Repurpose It" and "Tyrecycle", respectively, and the authors wish to thank them. The authors wish to acknowledge the input from Dr Mahdi Disfani of Melbourne School of Engineering.

#### REFERENCES

- AS1289.3.5.1 (2006) Methods of Testing of Testing Soils for Engineering Purposes- Soil classification tests - Determination of the soil particle density of a soil- Standard method. Sydney, Australia: Standards Association of Australia.
- AS1289.5.1.1 (2017) Methods of Testing of Testing Soils for Engineering Purposes- Soil compaction and density tests- Determination of the dry density/ moisture content relation of a soil using standard compactive effort. Sydney, Australia: Standards Association of Australia.
- AS1289.5.5.1 (2016) Methods of testing soils for engineering purposes: Soil compaction and density tests - Determination of the minimum and maximum dry density of a cohesionless material - Standard method. Sydney, Australia: Standards Association of Australia.
- AS1289.6.6.1 (1998) Methods of testing soils for engineering purposes-Soil strength and consolidation tests—Determination of the one-dimensional consolidation properties of a soil—Standard method. Sydney, Australia: Standards Association of Australia.
- Attom, M. F. J. E. G. (2006). "The use of shredded waste tires to improve the geotechnical engineering properties of sands." 49(4), 497-503.
- Fauzi, A., Djauhari, Z. and Fauzi, U. J. (2016). "Soil engineering properties improvement by utilization of cut waste plastic and crushed waste glass as additive." 8(1), 15.
- Imteaz, M. A., Ali, M. Y., Arulrajah, A. J. W. m. and research (2012). "Possible environmental impacts of recycled glass used as a pavement base material." 30(9), 917-921.
- Imteaz, M. A., Arulrajah, A., Horpibulsuk, S. and Ahsan, A. J. I. J. o. E. R. (2018). "Environmental Suitability and Carbon Footprint Savings of Recycled Tyre Crumbs for Road Applications." 12(5), 693-702.
- Islam, M. (2015) "A study of volumetric behaviour of compacted clayey soils in the void ratio, moisture ratio and net stress space" Thesis, Monash University. Faculty of Engineering. Department of Civil Engineering.
- Kamaruddin, M., Abdullah, M., Zawawi, M. H. and Zainol, M. (2017). Potential use of plastic waste as construction materials: recent progress and future prospect, *IOP Conference Series: Materials Science and Engineering*. IOP Publishing Ltd.
- Landris, T. L. (2007). "Recycled glass and dredged materials." *US Army Corps of Engineers, Engineer Research and Development Center, Mississippi, USA. Report No. ERDC TN-DOER-T8*.
- Lindsey, T. C.(2011). "Sustainable principles: common values for achieving sustainability." *Journal of Cleaner Production*, 19(5), 561-565.
- MRWA (2013): "*Backfill Specification-Specification 04-03.2*". Melbourne Water Retail Agencies.
- Su, N. and Chen, J. S. (2002). "Engineering properties of asphalt concrete made with recycled glass." 35(4), 259-274.
- Tripathy, S., Subba Rao, K. S. and Fredlund, D. G. (2002). "Water content - Void ratio swell-shrink paths of compacted expansive soils." *Canadian Geotechnical Journal*, 39(4), 938-959.
- VicRoads (2013) Section 815: Cementitious treated crushed rock for pavement subbase. Kew, VIC, Australia.